



Forward GEM Tracker (FGT)

Technical implementation, Cost, R&D plan, Schedule

Bernd Surrow






Outline

- Technical realization



- Layout



- R&D plan
- Cost estimate
- Schedule

- Requirements



FGT group

□ Institution list

- Argonne National Laboratory
- Indiana University Cyclotron Facility
- Lawrence Berkeley National Laboratory
- Massachusetts Institute of Technology
- Valparasio University
- Yale University





Requirements

- **e^-/e^+ separation** for high- p_T tracks in STAR EEMC acceptance ($1 < \eta < 2$)
- **Material budget:** $< 10\%$ ($1 < \eta < 2$)
- **Rate capability:** Handle RHICII peak luminosities for p+p
- **Sampling speed:** Resolve individual beam bunches (107ns - bunch crossing time)

Layout

- Triple-GEM detector disks: Forward-GEM Tracker (FGT)

FGT Sketch




86cm

- FGT: 6 light-weight disks
- Each disk consists of 4 triple-GEM chambers

Technical realization

□ Mechanical design - Support structure





R&D plan

□ R&D items - 2007

○ The following R&D activities are foreseen in 2007

- Prototype and test FGT hybrid chip readout system
- Feasibility study on the usage of light-weight carbon foam material to design a triple-GEM prototype chamber including support structure
- Feasibility study on the usage of laser-etched readout board optimized for hit resolution requirement and STAR conditions
- Explore the usage of air cooling
- Stability of carbon foam material

○ Requested funds: \$120k

- R&D Engineering research: \$75k
- Readout components (APV25-S1 chip, cables, hybrids): \$15k
- Carbon foam material, air cooling and readout board: \$30k and larger GEM foils (SBIR effort)



R&D plan

□ R&D items - 2008

○ The following R&D activities are foreseen in 2008

□ Test hybrid chip readout system and STAR DAQ integration

□ Investigate performance of triple-GEM light-weight prototypes on the bench

□ Investigate performance of triple-GEM light-weight prototypes chamber inside STAR under beam conditions

○ Requested funds: \$125k

□ R&D engineering research: \$100k

□ STAR beam test: \$25k



Cost estimate

□ FGT cost estimate assumptions

- Estimate is based on **baseline design**
- The **readout system** is based on the **APV25-S1** chip which is already part of a prototype readout system (**PHOBOS expertise** at LNS on chip readout systems)
- Current estimate relies heavily on the **collaboration with Tech-Etch Inc.** as part of the ongoing SBIR program



Cost estimate

□ Material

Item	Amount	k\$
GEM chamber mechanics	36	51
Readout board	36	51
GEM foils	150	42
APV25-S1 chips	828	29
Flex cable/hybrid	75	21
Control Units	15	8.4
Ribbon cables	15	2.8
LV power supplies	2	20
HV power supplies	2	11
DAQ		200
Air cooling		35
Mechanics		250
Misc. items (Incl. gas system)		70
Total		791
Grand total		862

Spares:

- GEM foils (42/150)
- GEM chamber mechanics (12/36)
- 50% spares: Readout chips, flex cables/hybrids, control units and ribbon cables

Contingency:

- 20% on catalogue items and 40% on non-standard items

Allocation:

- 9% of Total



Cost estimate

- Mechanical engineering
 - MIT-Bates mechanical engineering division: MIT
- Electronics engineering
 - ANL and MIT-Bates electronics engineering division: ANL / MIT
- GEM lab
 - LNS and Yale laboratory: MIT / Yale
- Assembly and integration: MIT / BNL
- Computing / Software: IUCF / LBL / MIT
- DAQ integration: ANL / MIT



Cost estimate

□ Labor

Institute (6)	MIT (4)	BNL (2)
Mechanical FTE (3) (Engineer / Technician)	1 (\$200k) / 1 (\$100k)	0.5 (\$100k) / 0.5 (\$50k)
Electrical FTE (3) (Engineer / Technician)	1 (\$200k) / 1 (\$100k)	0.5 (\$100k) / 0.5 (\$50k)
Total:	\$400k / \$200k	\$200k / \$100k

(1 FTE: 1 Full-Time Employee per year including overhead)

Total: \$1170k (With 30% contingency)

Total FGT project cost: Material (\$862k) + Labor (\$1170k) = \$2032k

(Estimated contributed labor (Not subtracted): 0.5 FTE (Technician))



Schedule

□ FGT work flow (In weeks)

- Design phase (Support structure / Triple-GEM chambers): 12 weeks
- Procurement of material: 6 weeks
- Construction of detector quarter sections: 18 weeks
 - Delivery of 10 GEM foils from Tech-Etch per week
 - Test of GEM foils (Electrical tests, optical scan on flatbed scanner): 0.5 week
 - Test of readout board (Parallel to GEM foil tests): 0.5 week
 - Construction of GEM detectors: Mechanical assembly, foil mounting, testing between each gluing step: 2 weeks
 - Test of assembled chamber: Gas tightness, X-ray test, Gain map: 2 weeks
 - Estimated total construction of one quarter section: 5 weeks
 - Assume: 2 detectors in parallel starting every week
- Construction of full system: 10 weeks
 - Assemble 6 disks on support frame from 4 quarter sections each: 1 week
 - Assemble electronics and test: 2 weeks
 - Test disk electronics and detectors and full system test (Cosmic ray test): 7 weeks
- Installation: 3 weeks
- Integration: 5 weeks

Total: $12 + 42 = 54$ weeks



Schedule

□ Realization

- If FGT project is $>2M\$$ DOE line item, construction may begin in October 2008 (FY09) - Installation only in summer 2010
- If FGT project is $<2M\$$, explore with BNL and DOE if there is any way to accelerate the schedule - Potential for installation before summer 2010
- RHIC schedule and Beam-Use request is still subject to ongoing discussion - Strong push to start before summer 2010 with 500 GeV CME polarized pp program
- Ideally: Complete installation of FGT with beginning of 500 GeV CME polarized pp program